Cobble Tail Ridge

Counterse Slating.

Copper Eaves Gutter

Stucco on 12" Hollow Tile
Tile face 11" in front of C. of L.

Wood frames & Mullions

Leaded Glass

Copper Gutter

Cantera Rubble Coursing

14" in front of C. of L.

Copper Flashing

ELEVATOR MACHINERY PENT HOUSE

Copper R. W. Head & Down Pipe

Stucco on Tile.
Tile face 12" in front of C. of L.

Verticaly Pivoted Sash with Copper Mosquito Mesh

Ventilator

Tile Weathering

Slate roofs over Entrance Lobby

Copper Sill.

Lintels for future Extension

Slate R. C. Lintels over Windows.

Granite Threshold

TEMPORARY PERIODICAL READING ROOM.

Magazine Racks (2 deep)

TEMPORARY WOMENS REST RM.

Temporary Steel Partition with Leadening Quilt

TEMPORARY CATALOGUE ROOM.

Metal Screen

THE STACK ROOM.

BOOK STACKS, IRON STAIR, MARBLE FLOOR AND SUPPORTS IN STEEL BOOK STACK CONTRACT.

LIFT

BOOK

2'6" WIDE

Stair enclosed in Tile Iron

IRON STAIRCASE

ELEVATOR

SHAFT

Section thro' S. Wall of Stairs.

Half Elevation.

Half Section.

STACK ROOM.

REGISTERED ARCHITECTS SHARP & THOMPSON VANCOUVER BRITISH COLUMBIA

Scale 1/4"=1 foot December 17, 1923	UNIVERSITY of B.C. The LIBRARY BLDG	Sharp & Thompson M.R.A.I.C. Architects 626 Hastings Street Vancouver B.C.	9 Print No.