



**NOTES**

- ① SEE SHEET NO. 13 FOR DETAILED CHANGES IN NEW CATALOGUING & ACQUISITIONS.
- ② DEMOLITION, NEW PARTITIONS, RE-LIGHTING, NEW FLOOR, NEW SHELVING, REQUIRED IN NEW READING ROOM SEE DETAILS SHEET NO. 13.
- ③ SEE SHEET NO. 13 FOR MILLWORK ELEVATIONS AND DETAILS OF FINISHES THIS AREA.
- ④ APPLY ACOUSTIC TILE AS SPEC. TO CEILING, RE-LIGHT AND FINISH AS NOTED ON SHEET NO. 13.
- ⑤ REMOVE CLAY TILE PROJECTION AND MOVE DUCT WITHIN TO WEST AS REQUIRED TO FINISH OPENING OF STAIRS AS SPECIFIED. THIS TREATMENT TO BE CARRIED UP STAIRWAY TO TOP FLOOR.
- ⑦ ⑧ ⑨ CARRY OUT WORK IN GENERAL OFFICE AREA AS DESCRIBED AND DETAILED SHEET NO. 12. THIS TO INCLUDE NEW PARTITIONS SHOWN, NEW FLOORING, RE-LIGHTING, SUSPENDED CEILING AS SPEC.
- ⑩ RE-LOCATE PLUMBING IN GEN. STAFF LAV TO MAKE WAY FOR BOOK DEPOSITORY, INSTALL BOOK DEPOSITORY ALL AS DETAILED SHEET NO. 11.
- ⑪ DEMOLISH PARTITIONS, RE-FLOOR & RE-LIGHT, INSTALL MILLWORK ALL AS DETAILED SHEET NO. 11.
- ⑫ INSTALL NEW SHELVING IN RENOVATED FIREPROOF STORAGE VAULT. SEE SHEET NO. 11.
- ⑬ PROVIDE ACOUSTICALLY SHAPED, ISOLATED, PIANO ROOM WITH DOUBLE DOORS ALL AS DETAILED SHEET NO. 11.
- ⑭ CUT NEW DOORWAY INTO STACK AREA AS SHOWN ON SHEET NO. 11 (THIS WORK COMPL. JAN. 1960)
- ⑮ PARTITION OFF PORTIONS OF EXISTING STACK AREA WITH CHAIN LINK MESH RUNNING FROM FLOOR TO CEILING.

1	JAN. 1960	ALTERATIONS TO EXISTING BLDG. - NOTE #1-#15
No.	DATE	REVISION

**THOMPSON, BERWICK & PRATT**  
 ARCHITECTS  
 1555 ROBSON ST. VANCOUVER 5, B. C.

ADDITIONS & ALTERATIONS TO THE LIBRARY  
 UNIVERSITY OF BRITISH COLUMBIA  
 PLAN - STACK LEVEL #3  
 DRAWN: C.H.F. FB. CHECKED: E.P.A. SCALE: AS SHOWN DATE: MAY 15, 1959

SHEET No.  
**3**  
 OF